




ENLARGED FIRST FLOOR PLUMBING DEMO PLAN
SCALE: 1/4"=1'-0"




ENLARGED FIRST FLOOR SANITARY PLAN
SCALE: 1/4"=1'-0"




ENLARGED FIRST FLOOR DOMESTIC WATER PLAN
SCALE: 1/4"=1'-0"



ENLARGED SECOND FLOOR PLUMBING DEMO PLAN
SCALE: 1/4"=1'-0"



ENLARGED SECOND FLOOR SANITARY PLAN
SCALE: 1/4"=1'-0"



ENLARGED SECOND FLOOR DOMESTIC WATER PLAN
SCALE: 1/4"=1'-0"

KEY NOTES (DEMO PLAN)

- EXISTING LAVATORY TO BE REMOVED. REMOVE EXISTING TRAP, TAIL PIECE, WASTE ARM, WALL ESCUTCHEON, FLEX SUPPLIES, STOP VALVES, ETC. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FUTURE. PROVIDE NEW WASTE ARM, WALL ESCUTCHEON, TRAP WITH CLEANOUT, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS FOR ALL LAVS AND INSULATION KITS FOR ACCESSIBLE LAVS.
- EXISTING FLOOR MOUNT WATER CLOSET TO BE REMOVED. REMOVE EXISTING FIXTURE, EXPOSED HARDWARE AND VALVES. MODIFY EXISTING SANITARY, VENT, DOMESTIC, COLD WATER LINES, ETC. AS REQUIRED TO ALLOW FOR NEW FUTURE.
- EXISTING BATH/TUB TO BE REMOVED. REMOVE EXISTING HARDWARE AND VALVES, ETC. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FUTURE.
- EXISTING KITCHEN SINK TO BE REMOVED. REMOVE EXISTING TRAP, TAIL PIECE, WASTE ARM, WALL ESCUTCHEON, FLEX SUPPLIES, STOP VALVES, ETC. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FUTURE.
- EXISTING WATER HEATER TO BE REMOVED. MODIFY EXISTING DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW WATER HEATER. PROVIDE NEW VALVES, EXPANSION TANK, RELIEF VALVES, ETC.

KEY NOTES (SAN. & DW PLAN)

- NEW LAVATORY TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FUTURE. PROVIDE NEW WASTE ARM, WALL ESCUTCHEON, TRAP WITH CLEANOUT, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS FOR ALL LAVS AND INSULATION KITS FOR ACCESSIBLE LAVS.
- NEW FLOOR MOUNTED WATER CLOSET TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT, DOMESTIC, COLD WATER LINES, ETC. AS REQUIRED TO ALLOW FOR NEW FUTURE. PROVIDE NEW WASTE ARM, TAILPIECE, STOP VALVES AND FAUCETS FOR ALL SHOWERS.
- NEW SHOWER TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FUTURE. PROVIDE NEW WASTE ARM, TAILPIECE, STOP VALVES AND FAUCETS FOR ALL SHOWERS.
- NEW KITCHEN SINK TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FUTURE. PROVIDE NEW WASTE ARM, WALL ESCUTCHEON, TRAP WITH CLEANOUT, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS.
- NEW HOT WATER HEATER TO BE INSTALLED. MODIFY EXISTING DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW WATER HEATER. PROVIDE NEW VALVES, EXPANSION TANK, RELIEF VALVES, ETC.
- NEW FLOOR DRAIN TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT, DOMESTIC COLD WATER LINES, ETC. AS REQUIRED TO ALLOW FOR NEW FLOOR DRAIN. PROVIDE FLOOR DRAIN WITH NEW TRAP PRIMERS.

Revisions

Date	Issue	Description
03-06-15	1	ISSUED FOR DCA FILING
03-18-15	2	ISSUED FOR BIDDING

Consultants

LINWOOD ENGINEERING ASSOCIATES, P.A.

CONSULTING MECHANICAL & ELECTRICAL ENGINEERS

LEA 955 Lincoln Ave. 2301 Dupont Drive-Suite 150
Glen Rock, New Jersey Irvine, California
07452 92512
t: 201.857.3998 f: 714.424.0001
t: 201.857.3994 f: 714.424.0004
www.linwoodengineering.com

Michael T. Davina, P.E. Robert J. Hatch, P.E.

NJ #48654 AR #13868
CT #0025779 CA #E16118
CT #13318 FL #69560
MA #48516
NJ #30419
NV #019975
NY #56608
PA #036014-E

Project

INTERIOR RENOVATIONS
AT THE
MIMOSA - G RESIDENCE

RAMAPO COLLEGE
OF NEW JERSEY
505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

Client

RAMAPO COLLEGE
OF NEW JERSEY
505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

SNS Architects & Engineers, PC

1 PARAGON DRIVE . MONTVALE . NEW JERSEY . 07645
tel: 201.573.1767 fax: 201.573.0808 www.sns-arch-eng.com

Fay W. Logan, AIA
John M. Lignos, AIA
Lorin J. Sonenshine, AIA
Steven Napolitano, PE

Cert./Lic. No.
Date 02-03-15 Scale AS NOTED
Drawn By MD Checked By SG

Dwg. Title
ENLARGED FIRST & SECOND FLOOR
PLUMBING PLANS

Work Order No. Dwg. No.

4698G P200