

LIGHTING NOTES:

- WHERE EXISTING WIRING AND CIRCUITRY WHICH IS TO REMAIN IS LEFT EXPOSED BY DEMOLITION AND REMOVAL OF PARTITION AND/OR LUNG CELLS, REWIRE SUCH WIRING TO MAINTAIN THE CIRCUIT CONTINUITY.
- WHERE EXISTING WIRING AND CIRCUITRY TO REMAIN IS LEFT STUBBED UP FROM FLOOR BY THE DEMOLITION AND REMOVAL OF PARTITIONS, REWIRE SUCH WIRING AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY AND CUT BACK CONDUIT BELOW TOP OF FINISHED SLAB TO PREVENT FLOORING.
- WHERE EXISTING CIRCUITRY IS BEING UTILIZED FOR CONNECTION OF NEW LOAD OR BEING RETAINED FOR EXISTING LOADS AND SUCH CIRCUITRY IS NOT EXACTLY AS INDICATED ON PLANS, MAKE SUCH MODIFICATIONS AS MAY BE REQUIRED TO ACCOMPLISH THE DESIGN INTENT.
- WHERE EXISTING LIGHTING EQUIPMENT, WIRING, ETC. IS INDICATED AS REMAINING AND SUCH ITEMS INTERFERE WITH THE INSTALLATION OR THE DEMOLITION MARK OF OTHER TRADES, DISCONNECT, REMOVE, AND RELOCATE TO AVOID CONFLICTS. REINSTALL AND REWIRE SUCH ITEMS AS REQUIRED.
- WHERE EXISTING FIXTURES ARE BEING REMOVED AND SUCH REMOVAL DISTURBS THE CIRCUITRY TO FIXTURES WHICH ARE TO REMAIN, PROVIDE ALL NECESSARY MODIFICATIONS AND ADDITIONS TO WIRING AS REQUIRED TO RETAIN SERVICE AND SWITCH CONTROL FOR REMAINING FIXTURES.
- NUMBERS INDICATED FOR BRANCH CIRCUITS ARE FOR GROUPING ONLY.
- ALL PANEL BOARD WIRING/LOOPS ARE TO BE UPDATED FOR FUTURE REFERENCE.

MATCH
LINE

FIRST FLOOR LIGHTING PLAN


SCALE: 1/4"=1'-0"

MATCH
LINE

Revisions

| Date | Issue | Description |
|----------|-------|------------------------|
| 08-03-15 | 1 | ISSUE FOR CONSTRUCTION |

Key Plan



Consultants

LINWOOD ENGINEERING ASSOCIATES, P.A.

LEA CONSULTING MECHANICAL & ELECTRICAL ENGINEERS
955 Lincoln Ave. Glen Rock, New Jersey 07452
2301 Dupont Drive-Suite 150 Irvine, California 92612
t: 201.857.3998 f: 714.424.0001
t: 201.857.3994 f: 714.424.0004
www.linwoodengineering.com

Michael T. Davina, P.E.

NJ #48654
CT #0025779

Robert J. Hatch, P.E.

AR #13868
CA #E16118
CT #13318
FL #69560
MA #48516
NJ #30419
NV #019975
NY #56608
PA #036014-E

Project

INTERIOR RENOVATIONS
AT THE
TAMARACK - N RESIDENCE
RAMAPO COLLEGE
OF NEW JERSEY
505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

Client

RAMAPO COLLEGE
OF NEW JERSEY
505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

SNS Architects & Engineers, PC

1 PARAGON DRIVE, MONTVALE, NEW JERSEY 07645
tel: 201.573.1767 fax: 201.573.0808 www.sns-arch-eng.com

- Fay W. Logan, AIA ☐
- John M. Lignos, AIA ☐
- Lorin J. Sonenshine, AIA ☐
- Steven Napolitano, PE ☐

Cert./Lic. No. _____

Date 04-10-15 Scale AS NOTED

Drawn By MD Checked By SE

Dwg. Title

FIRST FLOOR LIGHTING PLAN

Work Order No. _____ Dwg. No. _____

4698N E200