


MATCH  
LINE



**LIGHTING NOTES:**

- WHERE EXISTING WIRING AND CIRCUITRY WHICH IS TO REMAIN IS LEFT EXPOSED BY DEMOLITION AND REMOVAL OF PARTITION AND/OR HANG CEILING, REROUTE SUCH WIRING TO MAINTAIN THE CIRCUIT CONTINUITY.
- WHERE EXISTING WIRING AND CIRCUITRY TO REMAIN IS LEFT COVERED UP FROM FLOOR BY THE DEMOLITION AND REMOVAL OF PARTITIONS, REROUTE SUCH WIRING AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY AND GET BACK OUTSIDE BELOW TOP OF FINISHED SLAB TO PREVENT TRIPPING.
- WHERE EXISTING CIRCUITRY IS BEING UTILIZED FOR CONNECTION OF NEW LOAD OR BEING RETAINED FOR EXISTING LOADS AND SUCH CIRCUITRY IS NOT EXACTLY AS INDICATED ON PLANS, MAKE SUCH MODIFICATIONS AS MAY BE REQUIRED TO ACCOMPLISH THE DESIGN INTENT.
- WHERE EXISTING LIGHTING EQUIPMENT, WIRING, ETC., IS INDICATED AS REMAINING AND SUCH ITEMS INTERFERE WITH THE INSTALLATION OR THE DEMOLITION WORK OF OTHER TRADES, DISCONNECT, REMOVE, AND RELOCATE TO AVOID CONFLICTS. REINSTALL AND RECONNECT SUCH ITEMS AS REQUIRED.
- WHERE EXISTING FIXTURES ARE BEING REMOVED AND SUCH REMOVAL DISTURBS THE CIRCUITRY TO FIXTURES WHICH ARE TO REMAIN, PROVIDE ALL NECESSARY MODIFICATIONS AND ADDITIONS TO WIRING AS REQUIRED TO RETAIN SERVICE AND SWITCH CONTROL FOR REMAINING FIXTURES.
- NUMBERS INDICATED FOR BRANCH CIRCUITS ARE FOR GROUPING ONLY.
- ALL PANELBOARD DISCRETEURES ARE TO BE UPDATED FOR FUTURE REFERENCE.

MATCH  
LINE


**THIRD FLOOR LIGHTING PLAN**

SCALE: 1/4"=1'-0"

**Revisions**

Date	Issue	Description
06-03-15	1	ISSUE FOR CONSTRUCTION

**Key Plan**



**Consultants**

**LINWOOD ENGINEERING ASSOCIATES, P.A.**

CONSULTING MECHANICAL & ELECTRICAL ENGINEERS

**LEA** 955 Lincoln Ave. 2301 Dupont Drive-Suite 150  
Glen Rock, New Jersey Irvine, California  
07452 92612  
t: 201.857.3998 t: 714.424.0004  
f: 201.857.3994 f: 714.424.0004  
www.linwoodengineering.com

**Michael T. Davina, P.E. Robert J. Hatch, P.E.**

NJ #48654 CT #0025779	AR #13868 CA #E16118 CT #13318 FL #69560 MA #48516 NJ #30419 NV #019975 NY #56608 PA #036014-E
--------------------------	--

**Project**

INTERIOR RENOVATIONS  
AT THE  
**TAMARACK - N RESIDENCE**



**Client**



**SNS Architects & Engineers, PC**

1 PARAGON DRIVE, MONTVALE, NEW JERSEY 07645  
tel: 201.573.1767 fax: 201.573.0808 www.sns-arch-eng.com

Fay W. Logan, AIA	○
John M. Lignos, AIA	○
Lorin J. Sonenshine, AIA	○
Steven Napolitano, PE	○

Cert./Lic. No.	
Date 04-10-15	Scale AS NOTED
Drawn By MD	Checked By SE
Dwg. Title	
THIRD FLOOR LIGHTING PLAN	

Work Order No. Dwg. No.

4698N E202