


**POWER PLAN NOTES:**

- WHERE EXISTING WIRING AND CIRCUITRY WHICH IS TO REMAIN IS LEFT EXPOSED BY DEMOLITION AND REMOVAL OF PARTITION AND/OR HINGE CEILING, REWIRE SUCH WIRING TO MAINTAIN THE CIRCUIT CONTINUITY.
- WHERE EXISTING WIRING AND CIRCUITRY TO REMAIN IS LEFT SHIPPED UP FROM FLOOR BY THE DEMOLITION AND REMOVAL OF PARTITIONS, REWIRE SUCH WIRING AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY AND CUT BACK CIRCUITRY BELOW TOP OF FINISHED SLAB TO PREVENT PATCHING.
- WHERE EXISTING CIRCUITRY IS BEING UTILIZED FOR CONNECTION OF NEW LOAD OR BEING RETAINED FOR EXISTING LOADS AND SUCH CIRCUITRY IS NOT EXACTLY AS INDICATED ON PLANS, MAKE SUCH MODIFICATIONS AS MAY BE REQUIRED TO WIRING TO ACCOMPLISH THE DESIGN INTENT.
- WHERE EXISTING LIGHTING EQUIPMENT, WIRING, ETC. IS INDICATED AS REMAINING AND SUCH ITEMS INTERFERE WITH THE INSTALLATION OR THE DEMOLITION WORK OF OTHER TRADES, DISCONNECT, REMOVE, AND RELOCATE TO AVOID CONFLICTS. REINSTALL AND RECONNECT SUCH ITEMS AS REQUIRED.
- WHERE EXISTING FIXTURES ARE BEING REMOVED AND SUCH REMOVAL DISTURBS THE CIRCUITRY TO FIXTURES WHICH ARE TO REMAIN, PROVIDE ALL NECESSARY MODIFICATIONS AND ADDITIONS TO WIRING AS REQUIRED TO RETAIN SERVICE, AND SWITCH CONTROL, FOR REMAINING FIXTURES.
- NUMBERS INDICATED FOR BRANCH CIRCUITS ARE FOR ORIGINATING ONLY.
- ALL PANELBOARD DIRECTORIES ARE TO BE UPDATED FOR FUTURE REFERENCE.
- CONTRACTOR SHALL COORDINATE ALL DATA LOCATIONS, DEVICES, WIRING, EQUIPMENT, ETC. WITH COLLEGE PRIOR TO INSTALLATION FOR CONNECTION TO CAMPUS SYSTEM.

**KEY NOTES:**

- EXISTING HOT WATER HEATER DISCONNECT SWITCH/BREAKER TO REMAIN. CONTRACTOR TO DISCONNECT EXISTING WATER HEATER TO ALLOW FOR REPLACEMENT AND RE-CONNECT UPON INSTALLATION.
- EXISTING HVAC UNIT DISCONNECT SWITCH/BREAKER TO REMAIN. CONTRACTOR TO RE-WIRE FROM PANELBOARD TO DISCONNECT SWITCH/BREAKER.



**SECOND FLOOR POWER PLAN**  
SCALE: 1/4"=1'-0"

Revisions

| Date     | Issue | Description            |
|----------|-------|------------------------|
| 08-03-15 | 1     | ISSUE FOR CONSTRUCTION |

Key Plan

Consultants

**LINWOOD ENGINEERING ASSOCIATES, P.A.**

CONSULTING MECHANICAL & ELECTRICAL ENGINEERS

**LEA** 955 Lincoln Ave. 2301 Dupont Drive-Suite 150  
Glen Rock, New Jersey Irvine, California  
07452 92612  
t: 201.857.3999 t: 714.424.0001  
f: 201.857.3994 f: 714.424.0004  
www.linwoodengineering.com

**Michael T. Davina, P.E.** **Robert J. Hatch, P.E.**

NJ #48654 AR #13868  
CT #0025779 CA #E16118  
CT #13318 FL #69560  
MA #48516  
NJ #30419  
NY #019975  
NY #56608  
PA #036014-E

Project

INTERIOR RENOVATIONS  
AT THE  
**TAMARACK - N RESIDENCE**

**RAMAPO COLLEGE**  
OF NEW JERSEY  
505 Ramapo Valley Road  
Mahwah, New Jersey 07430-1680

Client

**RAMAPO COLLEGE**  
OF NEW JERSEY  
505 Ramapo Valley Road  
Mahwah, New Jersey 07430-1680

**SNS** Architects & Engineers, PC

1 PARAGON DRIVE, MONTVALE, NEW JERSEY 07645  
tel: 201.573.1767 fax: 201.573.0808 www.sns-arch-eng.com

Fay W. Logan, AIA  
John M. Lignos, AIA  
Lorin J. Sonenshine, AIA  
Steven Napolitano, PE

Cert./Lic. No.  
Date 04-10-15 Scale AS NOTED  
Drawn By MD Checked By SG

Dwg. Title  
**SECOND FLOOR POWER PLAN**

Work Order No. 4698N Dwg. No. E301