


- KEY NOTES (SAN. & DW PLAN)**
- ① NEW LAVATORY TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FIXTURE. PROVIDE NEW WASTE ARM WALL ESQUIRE TRAP WITH GLENNCO, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS FOR ALL LAVS AND INSULATION KITS FOR ACCESSIBLE LAVS.
 - ② NEW FLOOR MOUNTED WATER CLOSET TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT, DOMESTIC COLD WATER LINES, ETC. AS REQUIRED TO ALLOW FOR NEW FIXTURE. PROVIDE NEW WASTE ARM WALL ESQUIRE TRAP WITH GLENNCO, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS FOR ALL SHOWERS.
 - ③ NEW SHOWER TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FIXTURE. PROVIDE NEW WASTE ARM WALL ESQUIRE TRAP WITH GLENNCO, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS FOR ALL SHOWERS.
 - ④ NEW KITCHEN SINK TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FIXTURE. PROVIDE NEW WASTE ARM WALL ESQUIRE TRAP WITH GLENNCO, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS.
 - ⑤ NEW HOT WATER HEATER TO BE INSTALLED. MODIFY EXISTING DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW WATER HEATER. PROVIDE NEW VALVES EXPANSION TANK, RELIEF VALVES, ETC.
 - ⑥ EXISTING FLOOR DRAIN TO REMAIN.
 - ⑦ NEW FLOOR DRAIN TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT, DOMESTIC COLD WATER LINES, ETC. AS REQUIRED TO ALLOW FOR NEW FLOOR DRAIN. PROVIDE FLOOR DRAIN WITH NEW TRAP PRIMER.

Revisions		
Date	Issue	Description
06-03-15	1	ISSUED FOR CONSTRUCTION
11-16-15	2	REVISED PER NJDOCA ELECTRONIC STAMP



Consultants

LINWOOD ENGINEERING ASSOCIATES, P.A.

CONSULTING MECHANICAL & ELECTRICAL ENGINEERS

LEA 955 Lincoln Ave. 2301 Dupont Drive-Suite 150
Glen Rock, New Jersey 07452 Irvine, California 92612
t: 201.857.3998 f: 714.424.0001
f: 201.857.3994 t: 714.424.0004
www.linwoodengineering.com

Project

INTERIOR RENOVATIONS
AT THE
TAMARACK - N RESIDENCE

RAMAPO COLLEGE
OF NEW JERSEY
505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

Client

RAMAPO COLLEGE
OF NEW JERSEY
505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

SNS Architects & Engineers, PC
1 PARAGON DRIVE . MONTVALE . NEW JERSEY . 07645
tel: 201.573.1767 fax: 201.573.0808 www.sns-arch-eng.com

Fay W. Logan, AIA ☐
John M. Lignos, AIA ☐
Lorin J. Sonenshine, AIA ☐
Steven Napolitano, PE ☐

Cert./Lic. No.
Date 04-10-15 Scale AS NOTED
Drawn By MD Checked By SG
Dwg. Title
THIRD FLOOR DOMESTIC WATER PLAN

Work Order No. 4698N Dwg. No. P302

Michael T. Davina, P.E.
NJ #48654
CT #0025779

Robert J. Hatch, P.E.
AR #13868
CA #E16118
CT #15318
FL #69560
MA #48516
NJ #35419
NV #019975
NY #56608
PA #036014-E

MATCH
LINE

THIRD FLOOR DOMESTIC WATER PLAN
SCALE: 1/4"=1'-0"