


KEY NOTES (SAN. & DW PLAN)

- 1) NEW LAVATORY TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FIXTURE. PROVIDE NEW WASTE ARM WALL ESCUTCHEON TRAP WITH CLEANSOT, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS FOR ALL LIVING AND INSULATION KITS FOR ACCESSIBLE LIVING.
- 2) NEW FLOOR MOUNTED WATER CLOSET TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT, DOMESTIC COLD WATER LINES, ETC. AS REQUIRED TO ALLOW FOR NEW FIXTURE. PROVIDE NEW WASTE ARM, TAILPIECE, STOP VALVES AND FAUCETS FOR ALL SHOWERS.
- 3) NEW SHOWER TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FIXTURE. PROVIDE NEW WASTE ARM, TAILPIECE, STOP VALVES AND FAUCETS FOR ALL SHOWERS.
- 4) NEW FLOOR MOUNTED ONE TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT AND DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW FIXTURE. PROVIDE NEW WASTE ARM WALL ESCUTCHEON TRAP WITH CLEANSOT, TAILPIECE, STOP VALVES, FLEX SUPPLIES AND FAUCETS.
- 5) NEW HOT WATER HEATER TO BE INSTALLED. MODIFY EXISTING DOMESTIC HOT AND COLD WATER LINES AS REQUIRED TO ALLOW FOR NEW WATER HEATER. PROVIDE NEW VALVES, EXPANSION TANK, RELIEF VALVES, ETC.
- 6) EXISTING FLOOR DRAIN TO REMAIN.
- 7) NEW FLOOR DRAIN TO BE INSTALLED. MODIFY EXISTING SANITARY, VENT, DOMESTIC COLD WATER LINES, ETC. AS REQUIRED TO ALLOW FOR NEW FLOOR DRAIN. PROVIDE FLOOR DRAIN WITH NEW TRAP PRIMERS.



Consultants

LINWOOD ENGINEERING ASSOCIATES, P.A.

CONSULTING MECHANICAL & ELECTRICAL ENGINEERS

LEA 955 Lincoln Ave. 2301 Dupont Drive-Suite 150
Glen Rock, New Jersey Irvine, California
07452 92512
t: 201.857.3998 t: 714.424.0001
f: 201.857.3994 f: 714.424.0004
www.linwoodengineering.com

Michael T. Davina, P.E. **Robert J. Hatch, P.E.**

NJ #48654 AR #13868
CT #0025779 CA #E16118
CT #13318 CT #13318
FL #69560 FL #69560
MA #48516 MA #48516
NJ #30419 NJ #30419
NV #019975 NV #019975
NY #56608 NY #56608
PA #036014-E

Project

INTERIOR RENOVATIONS
AT THE
TAMARACK - N RESIDENCE



505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

Client



505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

SNS Architects & Engineers, PC

1 PARAGON DRIVE . MONTVALE . NEW JERSEY . 07645
tel: 201.573.1767 fax: 201.573.0808 www.sns-arch-eng.com


Fay W. Logan, AIA ☐
John M. Lignos, AIA ☐
Lorin J. Sonenshine, AIA ☐
Steven Napolitano, PE ☐

Cert./Lic. No.
Date 04-10-15 Scale AS NOTED
Drawn By MD Checked By SG

Dwg. Title
SECOND FLOOR DOMESTIC WATER PLAN

Work Order No. Dwg. No.

4698N **P301**



MATCH
LINE

SECOND FLOOR DOMESTIC WATER PLAN

SCALE: 1/4"=1'-0"