


**ELECTRICAL DEMOLITION NOTES:**

- DO NOT CONSIDER DEMOLITION AND ALTERATION NOTES TO BE ALL INCLUSIVE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSPECT AND ASSESS EACH SPACE, AND TO FULFILL THE INTENT OF THE WORK INDICATED BY THE CONTRACT DOCUMENTS. VERIFY ALL DIMENSIONS WITHIN THE CONTRACT LIMITS, BRING DEVIATIONS FROM THE CONTRACT DOCUMENTS, NECESSITATED BY FIELD CONDITIONS TO THE ATTENTION OF THE ARCHITECT.
- CONTRACTOR SHALL DISCONNECT AND MAKE SAFE ALL AREAS PRIOR TO GENERAL DEMOLITION BY THE GENERAL CONTRACTOR. THIS SHALL INCLUDE ALL MECHANICAL EQUIPMENT, CONTROL SYSTEMS AND ACCESSORIES, ELECTRICAL EQUIPMENT, AND ACCESSORIES. DEMOLITION SHALL BE REFERRED TO MECHANICAL DRAWINGS FOR MECHANICAL EQUIPMENT REMOVAL DISCONNECT DEMOLITION.
- CONTRACTOR TO PROVIDE TEMPORARY LIGHTING & POWER IN AREA OF WORK. TEMPORARY LIGHTING IS TO REMAIN AT COMPLETION OF PROJECT. TEMPORARY LIGHTING SHALL PROVIDE A MINIMUM OF 30 FOOT-CANDELES THROUGHOUT AREA OF WORK.
- DO ALL NECESSARY DEMOLITION AND REMOVAL OF EXISTING LIGHTING, EXISTING FIRE ALARM SYSTEM AND ELECTRICAL EQUIPMENT AS REQUIRED.
- DEMOLITION TO BE PERFORMED AFTER NORMAL WORKING HOURS IF REQUIRED BY THE OWNER.
- REROUTE AND RECONNECT ALL CIRCUITING TO EXISTING LOADS WHICH ARE TO REMAIN IF SAME IS DISMISSED BY DEMOLITION WORK. PROVIDE NEW WORK RIGID, IF REQUIRED.
- CONDUITS COMING UP OUT OF FLOOR SLAB WHICH ARE TO BE REMOVED SHALL BE CUT BACK BELOW TOP OF FINISHED SLAB TO PERMIT PATCHING.
- DISCONNECT AND REMOVE ALL EXISTING WIRING AND EXPOSED CONDUITS NOT BEING RETAINED OR REUSED.
- REMOVE ALL DEVICES AND ASSOCIATED WIRING AND CONDUITS FROM EXISTING OUTLETS, SWITCHES, FIRE ALARM DEVICES, ETC. BEING REMOVED TO PERMIT PATCHING OVER THE ARCHITECTURAL SURFACE.
- WHERE EXISTING WIRING AND CIRCUITRY WHICH IS TO REMAIN IS LEFT EXPOSED BY DEMOLITION AND REMOVAL OF PARTITION AND/OR WING CEILING, REROUTE SUCH WIRING TO MAINTAIN THE CIRCUIT CONTINUITY.
- WHERE EXISTING LIGHTING EQUIPMENT, WIRING, ETC. IS INDICATED AS REMAINING AND SUCH ITEMS INTERFERE WITH THE INSTALLATION OR THE DEMOLITION WORK OF OTHER TRADES, DISCONNECT, REMOVE, AND RELOCATE TO AVOID CONFLICTS. REINSTALL, AND RECONNECT DATA ITEMS AS REQUIRED.
- WHERE EXISTING LIGHTING FIXTURES AND DEVICES ARE BEING REMOVED AND SUCH REMOVAL DISTURBS THE CATEGORY TO LIGHTING FIXTURES AND DEVICES WHICH ARE TO REMAIN, PROVIDE ALL NECESSARY MODIFICATIONS AND ADDITIONS TO WIRING AS REQUIRED TO REMAIN SERVICE AND SWITCH CONTROL.
- RELOCATE EXISTING ACTIVE OUTLET BOXES, JUNCTION BOXES, ETC., WHICH ARE RENDERED INACCESSIBLE BY NEW CONSTRUCTION.
- ALL EXISTING BRANCH CIRCUIT WIRING FROM RESIDENTIAL

**Revisions**

Date	Issue	Description
06-03-15	1	ISSUED FOR CONSTRUCTION
11-16-15	2	REVISED PER NJDOCA ELECTRONIC STAMP

**Key Plan**



**Consultants**

**LINWOOD ENGINEERING ASSOCIATES, P.A.**

CONSULTING MECHANICAL & ELECTRICAL ENGINEERS

**LEA** 955 Lincoln Ave. 2301 Dupont Drive-Suite 150  
Glen Rock, New Jersey Irvine, California  
07452 92512  
t: 201.857.3998 f: 714.424.0001  
t: 201.857.3994 f: 714.424.0004  
www.linwoodengineering.com

**Project**

INTERIOR RENOVATIONS  
AT THE  
TAMARACK - N RESIDENCE


**RAMAPO COLLEGE**  
OF NEW JERSEY  
505 Ramapo Valley Road  
Mahwah, New Jersey 07430-1680

**Client**

**RAMAPO COLLEGE**  
OF NEW JERSEY  
505 Ramapo Valley Road  
Mahwah, New Jersey 07430-1680

**SNS** Architects & Engineers, PC  
1 PARAGON DRIVE, MONTVALE, NEW JERSEY, 07645  
tel: 201.573.1767 fax: 201.573.0808 www.sns-arch-eng.com

Fay W. Logan, AIA  
John M. Lignos, AIA  
Lorin J. Sonenshine, AIA  
Steven Napolitano, PE



**Michael T. Davina, P.E.**  
NJ #48654  
CT #0025779

**Robert J. Hatch, P.E.**  
AR #13868  
CA #E16118  
CT #15318  
FL #69560  
MA #48516  
NJ #35419  
NY #019975  
PA #036014-E

Cert./Lic. No.	Date	Scale	A5 NOTED
	04-10-15		
Drawn By	MD	Checked By	SG

Dwg. Title  
**THIRD FLOOR ELECTRICAL  
DEMOLITION PLAN**

Work Order No. Dwg. No.

**4698N E102**

**THIRD FLOOR ELECTRICAL DEMOLITION PLAN**

SCALE: 1/4"=1'-0"