


MATCH
LINE



POWER PLAN NOTES:


- WHERE EXISTING WIRING AND CIRCUITRY WHICH IS TO REMAIN IS LEFT EXPOSED BY DEMOLITION AND/OR REMOVAL OF PARTITION AND/OR HANG CEILING, REWIRE SUCH WIRING TO MAINTAIN THE CIRCUIT CONTINUITY.
- WHERE EXISTING WIRING AND CIRCUITRY TO REMAIN IS LEFT COVERED UP FROM FLOOR BY THE DEMOLITION AND REMOVAL OF PARTITIONS, REWIRE SUCH WIRING AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY AND RUN BACK CONDUIT BELOW TOP OF FINISHED SLAB TO PERMIT FASING.
- WHERE EXISTING CIRCUITRY IS BEING UTILIZED FOR CONNECTION OF NEW LOAD OR BEING RETAINED FOR EXISTING LOADS, AND SUCH CIRCUITRY IS NOT EXACTLY AS INDICATED ON PLANS, MAKE SUCH MODIFICATIONS AS MAY BE REQUIRED TO WIRING TO ACCOMPLISH THE DESIGN INTENT.
- WHERE EXISTING LIGHTING EQUIPMENT, WIRING, ETC. IS INDICATED AS REMAINING AND SUCH ITEMS INTERFERE WITH THE INSTALLATION OR THE DEMOLITION WORK OF OTHER TRADES, DISCONNECT, REMOVE, AND RELOCATE TO AVOID CONFLICTS. REINSTALL AND RECONNECT SUCH ITEMS AS REQUIRED.
- WHERE EXISTING FIXTURES ARE BEING REMOVED AND SUCH REMOVAL DISTURBS THE CIRCUITRY TO FIXTURES WHICH ARE TO REMAIN, PROVIDE ALL NECESSARY MODIFICATIONS AND ADDITIONS TO WIRING AS REQUIRED TO RETAIN SERVICE AND SWITCH CONTROL FOR REMAINING FIXTURES.
- NUMBERS INDICATED FOR BRANCH CIRCUITS ARE FOR GROUPING ONLY.
- ALL PANELBOARD DISCONNECTS ARE TO BE UPDATED FOR FUTURE REFERENCE.
- CONTRACTOR SHALL COORDINATE ALL DATA LOCATIONS, DEVICES, WIRING, EQUIPMENT, ETC. WITH COLLEGE PRIOR TO INSTALLATION FOR CONNECTION TO CAMPUS SYSTEM.

KEY NOTES:

- EXISTING HOT WATER HEATER DISCONNECT SWITCH/BREAKER TO REMAIN. CONTRACTOR TO DISCONNECT EXISTING WATER HEATER TO ALLOW FOR REPLACEMENT AND RE-CONNECT UPON INSTALLATION.
- EXISTING HVAC UNIT DISCONNECT SWITCH/BREAKER TO REMAIN. CONTRACTOR TO RE-WIRE FROM PANELBOARD TO DISCONNECT SWITCH/BREAKER.

Revisions		
Date	Issue	Description
06-03-15	1	ISSUED FOR CONSTRUCTION
11-16-15	2	REVISED PER NJDOCA ELECTRONIC STAMP

Key Plan



Consultants

LINWOOD ENGINEERING ASSOCIATES, P.A.

CONSULTING MECHANICAL & ELECTRICAL ENGINEERS

LEA 955 Lincoln Ave. 2301 Dupont Drive-Suite 150
Glen Rock, New Jersey Irvine, California
07452 92512
t: 201.857.3998 f: 714.424.0001
f: 201.857.3984 f: 714.424.0004
www.linwoodengineering.com

Project

INTERIOR RENOVATIONS
AT THE
TAMARACK - N RESIDENCE

RAMAPO COLLEGE
OF NEW JERSEY
505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

Client

RAMAPO COLLEGE
OF NEW JERSEY
505 Ramapo Valley Road
Mahwah, New Jersey 07430-1680

SNS Architects & Engineers, PC
1 PARAGON DRIVE, MONTVALE, NEW JERSEY, 07645
tel: 201.573.1767 fax: 201.573.0808 www.sns-arch-eng.com

Fay W. Logan, AIA
John M. Lignos, AIA
Lorin J. Sonenshine, AIA
Steven Napolitano, PE

Cert./Lic. No.
Date 04-10-15 Scale AS NOTED
Drawn By MD Checked By SG
Dwg. Title
THIRD FLOOR POWER PLAN

Work Order No. 4698N Dwg. No. E302

Michael T. Davina, P.E.
NJ #48654
CT #0025779

Robert J. Hatch, P.E.
AR #13868
CA #E16118
CT #15318
FL #69560
MA #48516
NJ #35419
NY #019975
PA #036014-E

MATCH
LINE

THIRD FLOOR POWER PLAN
SCALE: 1/4"=1'-0"